



NEPTUNE

Digital Adjustment Package Specification

Digital mixing system package shall include digital monitoring of the inlet, outlet temperatures via either the building management system or web-based interface. System shall have local digital temperature adjustment and local pump control. System shall provide continuous data logging, password protected control box and lock-out security key system. System shall maintain set temperature in the event of power loss to the system. Package shall be factory assembled and tested.

Unit supplied with the following:

- **Three Type J Thermocouple**
- **Modbus TCP/IP Protocol**
- **RJ-45 Communication Connection (Cable not included)**
- **Nema 4 ABS box attached with Stainless Steel Mounting Plate with 1/4" holes**
- **9 ft. 120 VAC Power Cord**
- **Pump switch box for local pump on/off capability**



MANUFACTURING CO., INC.

5330 East 25th Street
Indianapolis, Indiana 46218
Phone (317) 261-1212
Fax (317) 261-1208

Design and specification subject to change without notice.
Please refer to www.temperedwater.com to ensure most current data sheet and other design solutions